



ADDENDUM No. 3

TENDER # 2019 – 02

PINE AVENUE UTILITY AND STREETScape UPGRADE

Date: March 26, 2019

This addendum forms part of the Contract Documents and shall be read, interpreted, and coordinated with all other parts. The costs of all work contained herein shall be included in the Tender submission. The following revisions, clarifications, changes, additions, or deletions supersede the information contained in the original Documents to the extent referenced and shall become part thereof.

Addendum Items:

- 1. 50mm Watermain Tie-In – New Line Item and Clarification:** There is an existing 50mm diameter copper watermain that runs along Government St that needs to be tied into the proposed 200mm diameter C900 PVC watermain as shown on the construction drawings. The watermain pipe to tie the existing mains into the proposed watermain is accounted for in section 33 11 01 para 1.8.1, 1.8.2, "Watermain MST 200 PE 50mm diameter, All Depths, All Imported Backfill". However, the saddles, corporation stops and tie-ins have been missed. The below line item is to be submitted with the tender and will form a part of the Schedule of Quantities and Prices. This line item is to include all parts, labour, materials, and all other construction means to successfully install the 50mm watermain connecting it to the proposed watermain and the existing 50mm diameter copper watermain. This line item is considered a watermain and not a service, all other relevant sections, details, and drawings of the tender are to be considered when bidding on the below line item. The test point for this line item and this line item only, is to be incidental to the work and can be 50mm in diameter.

Section	Para	Specification Title	Unit	Quantity	Unit Price	Amount
33 11 01	1.8.18	50mm Watermain Tie-In	Each	4		

Please note that section 33 11 01, para 1.8.18SS "Existing Watermain Decommission" is to be changed to section 33 11 01 para 1.8.17SS and reference 33 11 01 WATERWORKS, 1.8 Measurement and payment, **Add Clause 1.8.17** of the Supplementary Specifications 2019 section of the tender.

Please note that Section 33 11 01, para 1.8.4, "Water Service Connections 50mm Diameter, As Per Typical Water Service Detail on Sheet C09" is for a 50mm diameter water service for the park on Pine Avenue located between addresses 371 and 361 Pine Avenue.

All of the above changes will be revised and issued upon project award.



2. **Existing Storm Main Decommission Deletion and Clarification:** Please remove para 1.6.2.3, "Existing Storm Main Decommission" from Section 33 40 01 of the Schedule of Quantities and Prices. All existing storm decommissioning costs are to be included in section 33 40 01, para 1.6.2.3SS, "Existing Storm Main Decommission".

The above change will be revised and issued upon project award.

3. **Watermain Tie-In Clarification:** Under Section 33 11 01, para 1.8.12 and 1.8.13 "Watermain Tie-in, Pipework by Contractor". One line item is for the watermain tie-in located at the intersection of Government St and Pine Avenue, and the other line item is for the watermain tie-in at the intersection of Government St, Pine Avenue, and Dogwood Avenue.

Addendum No. 3 is issued prior to receipt of tenders and shall form part of the Tender documents. The revisions shall supersede information contained in the original Tender Documents. Proponents must note receipt of this addendum below and attach this page to the Tender submission package.

Addendum No. 3 received.

Name of Tenderer

Engineering Technologist
Chris Desautels

CITY OF DUNCAN
200 Craig Street
Duncan, B. C.
V9L 1W3

Contract Administrator
Steven De Vries

CITY OF DUNCAN
200 Craig Street
Duncan, B. C.
V9L 1W3