

**GENERAL**

The following changes/clarifications in the RFQ documents are effective immediately. This Addendum will form part of the RFQ documents.

**Question:** Can you please advise what line item we are to place the costs associated with the line painting, asphalt curb and asphalt speed bump? Would this go under line item 3.2 - 50mm asphalt paving?

**Answer:** A new line item (3.12) has been created for Line Painting. Asphalt curb and speed bump costs to be included in asphalt paving (3.2)

**SCHEDULE OF QUANTITIES**

#	DESCRIPTION	QUANTITY	UNIT	RATE	TOTAL
1.0	<b>Earthworks</b>				
1.1	Removals (Bushes, Concrete, Fencing)	620	M2		
1.2	Subgrade prep and export (includes landscape area and raingarden)	620	M2		
2.0	<b>Underground Works</b>				
2.1	2 catch basins with outlet traps and 150mm and 200mm leads and connect to storm main	2	each		
2.3	Rain garden	1	each		
3.0	<b>Surface Works</b>				
3.1	Concrete Curb/Sidewalk/Access	33	M		
3.2	50mm asphalt paving	485	M2		
3.3	250mm – 75mm sub-base	485	M2		
3.4	100mm – 20mm base	485	M2		
3.5	Supply/install/relocate Bollards	LS			
3.6	Remove and relocate signs and banner pole	LS			
3.7	LED light c/w standard/base and conduit/junction boxes to service pole	LS			
3.8	Two Scarlett Oak trees 7cm caliper	2	each		
3.9	Ornamental Grasses	30	each		
3.10	200mm - growing medium	45	M2		
3.11	Adjust meter box/install new setter	LS			
3.12	Line Painting	LS			
				<b>SUBTOTAL</b>	
				<b>GST</b>	
				<b>TOTAL</b>	

**END OF ADDENDUM #1**