

**GENERAL**

Correction to Schedule of Quantities Item #1 quantity.

**SCHEDULE OF QUANTITIES**

#	DESCRIPTION	QUANTITY	UNIT	RATE	TOTAL
	<b><i>Underground Works</i></b>				
1.0	250 mm C-900 Watermain c/w associated gate valves, tees, spools, himax couplings, reducers, caps, thrust blocks, joint restrainers, etc. as per drawing and specifications.	58	m		
1.1	Hydrant c/w 7m-150mm lead	1	ea		
1.2	100mm Water service c/w flush-out/sidewalk box and re/re s/w panel	13	m		
1.3	Offset Air release valve c/w barrel, frame and lid	1	ea		
	<b><i>Surface Works</i></b>				
2.0	Boulevard/curb restoration	17	m2		
2.1	80mm asphalt paving patch	115	m2		
2.3	Supply/install/replace traffic loops/leads	4	ea		
				SUBTOTAL	
				GST	
				TOTAL	

**END OF ADDENDUM #1**