



ADDENDUM

Project:	North Beech Ave Renewal Project	Addendum No.:	02
Project No.:	221-01539-00	Date:	2022-September-01
Contract No.:			
Distribution:	John Pite, Manager of Engineering		

GENERAL

This Addendum forms part of the Contract Documents for the City of Duncan North Beech Ave Renewal Project and amends or clarifies the tender documents. The following revisions and/or clarifications supersede the information contained in the original Tender issued to the extent referenced and shall become part thereof. No adjustment to the Contract Price will be considered or allowed due to the Contractor or to any sub-contractor or supplier not being familiar with this Addendum.

- 1 Q :** Please confirm if we are to excavate, remove and dispose the existing subbase and base gravels after the existing asphalt has been removed.
A: Base Gravels to be excavate, removed, replaced and re-graded. Sub-base is assumed acceptable but must be approved via roll test prior to placement of base gravels. This price can be included in supplemental item B1: Asphalt Removal.
- 2 Q :** Please confirm the required thicknesses of new subbase and base gravels to asphalt areas.
A: 100mm Crushed Gravel Base and 200mm Sub-base on Approved Subgrade.
- 3 Q :** Please confirm thicknesses of base gravels beneath sidewalk, curb and driveway drops.
A: Per MMCD. 100mm Thick base gravels beneath sidewalk, curbs and driveway drops. Compacted to 95%MPD.
- 4 Q :** Please confirm if Beech Ave can be closed for duration of project.
A: No. Single lane, alternating traffic, to be maintained at all times. Beech Ave to remain accessible for homeowners and school at all times or closed for short intervals with 48hours notice. No short interval closures between 8:20-9:00am and 2:40-3:10pm.
- 5 Q :** Please confirm if parking considerations have been made for affected residents.
A: No additional parking considerations have been made.
- 6 Q :** Please confirm if temporary water supply to affected residents is expected.
A: Existing services to be maintained in place until new main and services are installed and tested. Daily shutdown may be necessary for turnover of service in which the contractor is to provide 48hrs notice.
- 7 Q :** Please confirm if there are any hours of work restrictions, when performing watermain, sanitary sewer and storm drain tie-ins on Trunk Rd.
A: Normal working hours remain for tie-ins on Trunk Rd.
- 8 Q :** Please confirm if we are to include soft landscape and fence repairs within the unit rates.
A: Address cost as required to suit as found or better condition.
- 9 Q :** Please confirm if soil environmental testing is to be completed by the contractor or the City, as dumpsites require this information prior to accepting the material.
A: Contractor is required to test for disposal as required. Include cost of testing/disposal within associated service installation line item or roadworks cost for excavation.

Suite 301, 3600 Uptown Boulevard
Victoria, BC, Canada V8Z 0B9

T: F +1 250 386-2844
www.wsp.com

ADDENDUM

10 Q : Please confirm if a bid bond is required.

A: Yes. Bid bond required. Noted as Bid Security in Tender Documents.

11 Q : Please confirm if the erosion and sediment control plan needs to be developed by a QEP

A : Yes, Contractor to hire a QEP to generate the ESC plan.

End of Addendum